

F

STING

# WESTERN ELECTRO - ACOUSTIC LABORATORY

CALIBRATION • RESEARCH

25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

## SOUND TRANSMISSION LOSS TEST REPORT NO. TL18-290

#### CLIENT: ClarkDietrich

9050 Centre Pointe Drive, #400 West Chester, Ohio 45069 TEST DATE: 16 June 2018 25 June 2018

### INTRODUCTION

The test was performed in accordance with ASTM E 90-09 (2016), *Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions* and ASTM E2235-04 (2012), *Standard Test Method for Determination of Decay Rates for Use in Sound Insulation Test Methods*. Copies of the test standard are available at <u>www.astm.org</u>. The test chamber source and receiving room volumes are 204 and 148.4 cubic meters respectively. Western Electro-Acoustic Laboratory is accredited by the United States Department of Commerce, National Institute of Standards and Technology under the National Voluntary Accreditation Program (NVLAP) Lab Code 100256-0 for this test procedure. This test report relates only to the item(s) tested. This report must not be used to claim product certification, approval, or endorsement by WEAL, NVLAP, NIST or any agency of the federal government.

### **DESCRIPTION OF TEST SPECIMEN**

The test specimen was a single stud wall assembly constructed from 38 mm by 89 mm (1-1/2 inch by 3-1/2 inch) wood studs, Owens Corning R-19 unfaced fiberglass batt insulation in the stud cavities, ClarkDietrich Acoustical Clips with 22 mm (7/8 inch) ClarkDietrich 25-gauge hat channel, and USG Sheetrock<sup>®</sup> Brand Firecode<sup>®</sup> Type 'X' gypsum board.

## **TEST CONFIGURATION**

Source Room Layers	Source Room Resilient Clip	Stud Configuration	Receiving Room Layers
2 layers 16 mm (5/8 inch) USG Sheetrock® Brand Firecode® Type 'X' gypsum board	ClarkDietrich Acoustical Clips with 22mm (7/8 inch) ClarkDietrich 25-gauge hat channel	38 mm by 89 mm (1-1/2 inch by 3-1/2 inch) wood studs with Owens Corning R-19 unfaced fiberglass batt insulation	2 layers 16 mm (5/8 inch) USG Sheetrock® Brand Firecode® Type 'X' gypsum board

The 38 mm by 89 mm (1-1/2 inch by 3-1/2 inch) wood studs were spaced 406 mm (16 inches) on center (O.C.). Owens Corning R-19 unfaced fiberglass batt insulation was installed in the stud cavities. The frame was isolated from the test opening with 6 mm (1/4 inch) neoprene pads.

- On the source side, ClarkDietrich Acoustical Clips were screwed to the studs using 64 mm (2-1/2 inch) #8 screws. The clips were installed 76 mm (3 inches) from the top and bottom of the wall with a maximum spacing of 1219 mm (48 inches) O.C. laterally and a maximum spacing of 610 mm (24 inches) vertically.
- On the source side, 22 mm (7/8 inch) ClarkDietrich 25-gauge hat channel was installed into the sound isolation clips.
- On the source side, two layers of 16 mm (5/8 inch) USG Sheetrock<sup>®</sup> Brand Firecode<sup>®</sup> Type 'X' gypsum board were screwed to the hat channel. The first layer was screwed using 25 mm (1 inch) long #6 drywall screws spaced 305 mm (12 inches) O.C. along the channel. The second layer was screwed using 41 mm (1-5/8 inch) long #6 drywall screws spaced 406 mm (16 inches) O.C. along the channel. The first layer of gypsum board was oriented horizontally. The second layer of gypsum board was oriented vertically.

Report must be distributed in its entirety except with written permission from Western Electro-Acoustic Laboratory  $Page \ 1 \ of \ 3$ 





STING

# WESTERN ELECTRO - ACOUSTIC LABORATORY

CALIBRATION • RESEARCH

25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

# SOUND TRANSMISSION LOSS TEST REPORT NO. TL18-290

#### CLIENT: ClarkDietrich

9050 Centre Pointe Drive, #400 West Chester, Ohio 45069 25 June 2018

TEST DATE: 16 June 2018

- On the receiving side, two layers of 16 mm (5/8 inch) USG Sheetrock<sup>®</sup> Brand Firecode<sup>®</sup> Type 'X' gypsum board were screwed to the studs. The first layer was screwed using 32 mm (1-1/4 inch) long #6 drywall screws spaced 305 mm (12 inches) O.C. along the perimeter and in the field. The second layer was screwed using 57 mm (2-1/4 inch) long #6 drywall screws spaced 305 mm (12 inches) O.C. along the perimeter and in the field with joints offset 305 mm (12 inches). The gypsum board was oriented vertically.
- All gypsum board joints were staggered on opposite sides. All the gypsum board joints were sealed with a bead of latex caulking and metal foil tape. All screw heads were covered with metal foil tape.
- On both sides around the perimeter of the assembly, a 6 mm (1/4 inch) gap was maintained and sealed with a bead of latex caulking and metal foil tape.
- The overall dimensions of the wall assembly were 2.44 m (96 inches) wide by 2.44 m (96 inches) high by 194 mm (7-5/8 inches) thick.
- The overall weight of the assembly was estimated to be 307 kg (676 lbs.) for a calculated surface density of 51.6 kg/m<sup>2</sup> (10.6 lbs./ft<sup>2</sup>).

## **RESULTS OF THE MEASUREMENTS**

One-third octave band sound transmission loss values are plotted and tabulated on the attached sheet. ASTM minimum volume requirements are met at 80 Hz and above. The Outdoor-Indoor Transmission Class rating determined in accordance with ASTM E 1332-10a was OITC-51. The Sound Transmission Class rating determined in accordance with ASTM E 413-10 was STC-62.

Approved:

Stephen A. Martin, Ph.D., P.E Laboratory Director

Respectfully submitted, Western Electro-Acoustic Laboratory

Raul Martinez Acoustical Test Technician





ΤΕ

S T I N G

# WESTERN ELECTRO - ACOUSTIC LABORATORY

• RESEARCH

25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

CALIBRATION


# SOUND TRANSMISSION LOSS TEST REPORT NO. TL18-290

#### CLIENT: ClarkDietrich

9050 Centre Pointe Drive, #400 West Chester, Ohio 45069 TEST DATE: 16 June 2018

•

25 June 2018



1/3 OCT BAND CNTR FREQ 100 125 160 200 250 315 400 500 63 80 35\* 45\* 49\* 60\* TL in dB 24 39 53\* 57\* 60\* 62\* 95% Confidence in dB 1.42 1.92 2.07 0.89 0.52 0.36 0.38 1.47 0.76 0.80 deficiencies (1)(0)(1)(0) 1/3 OCT BAND CNTR FREQ 4000 630 800 1000 1250 1600 2000 2500 3150 5000 TL in dB 63\* 67\* 69\* 67 66 58 65 67 66 63 95% Confidence in dB 0.29 0.44 0.38 0.39 0.36 0.56 0.55 0.31 0.32 0.50 deficiencies (0)(0)(8) (1)(0) EWR OITC Test Date: 16 June 2018 \* Minimum estimate of STC transmission loss. 64 51 Specimen Area: 64 sq.ft. 62 Measurement limited by filler wall. Temperature: 75.9 deg. F (11)Actual TL will be equal or greater than value Relative Humidity: 40 % eported

Report must be distributed in its entirety except with written permission from Western Electro-Acoustic Laboratory Page 3 of 3  $\,$ 

