

# CLARKDIETRICH BUILDING SYSTEMS, LLC ACOUSTICAL PERFORMANCE TEST REPORT

## **SCOPE OF WORK**

ASTM E90 AND ASTM E492 TESTING ON BARE GYPSUM FLOOR

## **SPECIMEN TYPE**

ClarkDietrich TradeReady® Steel Joist - 254 mm (10") - ClarkDietrich® Sound Clip - One-Layer USG SHEETROCK® Brand FIRECODE® C Core

#### REPORT NUMBER

J4775.01-113-11-R1

#### **TEST DATE**

03/19/19

**ISSUE DATE** 

**REVISED DATE** 

04/15/19

05/20/19

#### RECORD RETENTION END


03/19/23

#### **PAGES**

12

# **DOCUMENT CONTROL**

ATI 00629 (03/21/18) RTTDS-R-AMER-Test-2844 © 2017 INTERTEK





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

#### TEST REPORT FOR CLARKDIETRICH BUILDING SYSTEMS, LLC

Report No.: J4775.01-113-11-R1

Date: 05/20/19

#### **REPORT ISSUED TO**

**CLARKDIETRICH BUILDING SYSTEMS, LLC** 9100 Centre Pointe Drive, Suite 210 West Chester, Ohio 45069

# **SECTION 1**

#### **SCOPE**

Intertek Building & Construction (B&C) was contracted by ClarkDietrich Building Systems, LLC to perform testing in accordance with ASTM E90 AND ASTM E492 on Bare Gypsum Floor. Results obtained are tested values and were secured by using the designated test method(s). Testing was conducted in the VT test chambers at Intertek B&C located in York, Pennsylvania.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

#### **SECTION 2**

#### **SUMMARY OF TEST RESULTS**

DATA FILE NO.	J4775.01
SERIES/MODEL:	Bare Gypsum Floor
STC	54
IIC	43

**COMPLETED BY:** Cody R. Snyder **COMPLETED BY:** Daniel B. Mohler Technician - Acoustical Project Lead - Acoustical TITLE: TITLE: **Testing** Testing **SIGNATURE: SIGNATURE: DATE:** 05/20/19 DATE: 05/20/19

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of ACCREDITED the tested material, product or service must first be approved in writing by Intertek. The observations and test Testing Laborator results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# TEST REPORT FOR CLARKDIETRICH BUILDING SYSTEMS, LLC

Report No.: J4775.01-113-11-R1

Date: 05/20/19

#### **SECTION 3**

#### **TEST METHODS**

The specimen was evaluated in accordance with the following:

**ASTM E90-09 (2016)**, Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions

**ASTM E413-16**, Classification for Rating Sound Insulation

**ASTM E492-09(2016)e1**, Standard Test Method for Laboratory Measurement of Impact Sound Transmission Through Floor-Ceiling Assemblies Using the Tapping Machine

**ASTM E989-18**, Classification for Determination of Impact Insulation Class (IIC)

**ASTM E2235-04 (2012)**, Standard Test Method for Determination of Decay Rates for Use in Sound Insulation Test Methods

#### **SECTION 4**

#### MATERIAL SOURCE/INSTALLATION

The full test specimen was assembled on the day of testing by B&C. All materials provided by the client were installed on an existing B&C assembly (ClarkDietrich TradeReady® Steel Joist - 254 mm (10") - ClarkDietrich® Sound Clip - One-Layer USG SHEETROCK® Brand FIRECODE® C Core) utilizing B&C-supplied materials. The assembly was installed in a steel test frame which was installed into the opening between the source and receive rooms in the test chamber. The test frame was isolated from the structure with dense neoprene gasket.

The total weight of the floor/ceiling assembly was 841.1 kg / 1854.2 lbs. B&C will store samples of the test specimen for four years. Photographs of the test specimen are included in the report. The client did not supply drawings of the test specimen.

B&C will service this report for the entire test record retention period. Test records, such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation, will be retained by B&C for the entire test record retention period.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# TEST REPORT FOR CLARKDIETRICH BUILDING SYSTEMS, LLC

Report No.: J4775.01-113-11-R1

Date: 05/20/19

# **SECTION 5**

# **EQUIPMENT**

INSTRUMENT	MANUFACTURER	MODEL	DESCRIPTION	ASSET #	CAL DAT	Έ
Data Acquisition Unit	National Instruments	PXI-4462	Data Acquisition Card	INT00977	08/18	*
Data Acquisition Unit	National Instruments	PXI-4462	Data Acquisition Card	65124	05/18	*
Data Acquisition Unit	National Instruments	PXI-4462	Data Acquisition Card	63763-1	06/18	*
Microphone Calibrator	Norsonic	Nor1251	Acoustical Calibrator	65105	06/18	
Receive Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	65617	06/18	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	64340	09/18	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63745	06/18	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63746	09/18	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	63747	07/18	
Receive Room Environmental	Comet	T7510	Temperature and Humidity	63810	10/18	
Indicator	Comet	17510	Transmitter	63811	10/18	
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	63744	04/18	
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	63739	04/18	
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	63740	04/18	
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	INT00653	01/19	
Source Room Microphone	PCB Electronics	378C20	Microphone and Preamplifier	63741	04/18	
Source Room Environmental Indicator	Comet	T7510	Temperature and Humidity Transmitter	63812	10/18	
Tapping Machine	Norsonic	Nor277	Tapping Machine	INT00936	12/18	

<sup>\*</sup> The calibration frequency for this equipment is every two years per the manufacturer's recommendation.

VT RECEIVE ROOM VOLUME	156.8 m³ (5537.26 ft³)
VT SOURCE ROOM VOLUME	190 m³ (6709.79 ft³)

# **SECTION 6**

## **LIST OF OFFICIAL OBSERVERS**

NAME	COMPANY
Daniel R. Deickman	Intertek B&C
Daniel B. Mohler	Intertek B&C



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# TEST REPORT FOR CLARKDIETRICH BUILDING SYSTEMS, LLC

Report No.: J4775.01-113-11-R1

Date: 05/20/19

#### **SECTION 7**

#### **TEST PROCEDURE**

The microphones were calibrated before conducting the tests. The air temperature and relative humidity conditions were monitored and recorded during all measurements. The average temperature and humidity of both the source and received rooms are listed in Sections 10 and 11. The maximum and minimum temperatures and humidities of the receive room from the duration of the test are listed in Sections 12 and 13.

The airborne transmission loss test was conducted in accordance with the ASTM E90 test method using the single direction method. Two background noise sound pressure level and five sound absorption measurements were conducted at each of five microphone positions. Two sound pressure level measurements were made simultaneously in both rooms, at each of five microphone positions.

The impact sound transmission test was conducted in accordance with the ASTM E492 test method. Two background noise sound pressure level, two sound pressure level measurements with the tapping machine operating at each position specified by ASTM E492, and five sound absorption measurements were conducted at each of five microphone positions.

Detailed test procedures, data for flanking limit tests, repeatability measurements, and reference specimen tests are available upon request.

#### **SECTION 8**

#### **TEST CALCULATIONS**

The STC (Sound Transmission Class) and IIC (Impact Insulation Class) ratings were calculated in accordance with ASTM E413 and ASTM E989, respectively.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# TEST REPORT FOR CLARKDIETRICH BUILDING SYSTEMS, LLC

Report No.: J4775.01-113-11-R1

Date: 05/20/19

# **SECTION 9**

# **TEST SPECIMEN DESCRIPTION**

MATERIAL	Dimensions	Thickness	MANUFACTURER AND	QUANTITY	AVERAGE			
IVIATERIAL	(mm/inch)	(mm/inch)	SERIES	QUANTITI	WEIGHT			
	3023 by 3632	25.4 / 1	USG Levelrock® Brand	10.98 m²	45.89 kg/m <sup>2</sup>			
El ·	119 by 143	25.4 / 1	CSD® Early Exposure™	118.19 ft²	9.4 lb/ft <sup>2</sup>			
Floor Underlayment		•	loor underlayment, cured a n eter isolation. No noticeable s	hrinkage or crack				
	3023 by 1003.3	6.4 / 0.25	USG Levelrock® Brand SAM-		0.49 kg/m <sup>2</sup>			
Sound	119 by 39.5	0.4 / 0.23	N25™	118.19 ft²	0.1 lb/ft <sup>2</sup>			
Attenuation Mat	Note: Loose laid v	with seams overlap	pping and taped					
	3023 by 914.4	14.6 / 0.57	22-Gauge Corrugated	10.98 m²	6.7 kg/m <sup>2</sup>			
	119 by 36	14.0 / 0.57	22-Gauge Corrugated	118.19 ft²	1.37 lb/ft <sup>2</sup>			
Steel Floor Deck	depth of the deck mm (0.03").	Note: Installed in a test frame flush to the source room. Flutes filled with FIRM-FILL® CSD. The depth of the deck flutes was 14.3 mm (9/16") and the measured thickness of the metal was 0.7 mm (0.03").						
	520.7 by 3023	88.9 / 3.5	Johns Manville Unfaced R-	10.98 m²	1.32 kg/m <sup>2</sup>			
Fiberglass	20.5 by 119	00.5 / 3.5	13	118.19 ft²	0.27 lb/ft <sup>2</sup>			
Insulation	Note: Installed into the cavities between the joists, draped across furring/hat Channel.							
	3023 by 3632	254 / 10	Clark Diatrich Trade Deady®	21.16 lin m	4.78 kg/m			
Steel Joist	119 by 143	254 / 10	ClarkDietrich TradeReady®	69.42 lin ft	3.21 lb/ft			
Steel Joist	Note: Installed on 610 mm (24") centers using Trade Ready® rim track.							
Resilient Sound	76.2 by 36.5 3 by 1.4	31.8 / 1.25	ClarkDietrich® Sound Clip	24 clips	0.06 kg/clip 0.14 lb/clip			
Isolation Clip	Note: Installed in	Note: Installed in a 610 mm by 1219 mm (24" by 48") grid pattern.						
	3657.6 by 76.2	22.3 / 0.88	ClarkDietrich® 087F125-18	21.95 lin m	0.48 kg/m			
Furring/Hat	144 by 3		L	72 lin ft	0.32 lb/ft			
Channel	Note: Installed on 610 mm (24") centers perpendicular to the joists. The measured thickness of the metal was 0.7 mm (0.03").							
	1219 by 3023	15.0 / 0.63	USG SHEETROCK® Brand	10.98 m²	11.9 kg/m²			
	48 by 119	15.9 / 0.63	FIRECODE® C Core	118.19 ft²	2.44 lb/ft <sup>2</sup>			
Gypsum Panel	Note: Fastened to the channels on 203 mm (8") centers with 25.4 mm (1") Type S bugle head screws. The seams of the gypsum panels were sealed with Pecora AC-20 FTR caulk and covered with pressure sensitive tape.							



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# TEST REPORT FOR CLARKDIETRICH BUILDING SYSTEMS, LLC

Report No.: J4775.01-113-11-R1

Date: 05/20/19

## **SECTION 10**

# **TEST RESULTS - AIRBORNE SOUND TRANSMISSION LOSS**

TEST DATE DATA FILE NO.	3/19/2019 J4775.01				ACCREDITED	
CLIENT	ClarkDietrich Bu	arkDietrich Building Systems, LLC				
DESCRIPTION	N25™ Sound Attenuatio Unfaced R-13 Fiberglass Sound Clip Resilient Sou	ClarkDietrich Building Systems, LLC  5.4 mm (1") USG Levelrock® Brand CSD® Early Exposure™ Floor Underlayment, 6.4 mm (0.25") USG Levelrock® Brand SAM- 25™ Sound Attenuation Mat, 14.57 mm (0.57") 22-Gauge Corrugated Steel Floor Deck, 88.9 mm (3.5") Johns Manville nfaced R-13 Fiberglass Insulation, 254 mm (10") ClarkDietrich TradeReady® Steel Joist, 31.75 mm (1.25") ClarkDietrich® ound Clip Resilient Sound Isolation Clip, 22.3 mm (0.88") ClarkDietrich® 087F125-18 Furring/Hat Channel, 15.9 mm (0.63") SG SHEETROCK® Brand FIRECODE® C Core Gypsum Panel				
SPECIMEN AREA	10.98 m²	Receive Temp.	17.5°C (63.5°F)	Source Temp.	18.2°C (64.7°F)	
TECHNICIAN	DRD	Receive Humidity	52%	Source Humidity	52%	

FREQ	BACKGROUND	ABSORPTION	SOURCE	RECEIVE	SPECIMEN	95%	NUMBER
FREQ	SPL	ABSURPTION	SPL	SPL	TL	CONFIDENCE	OF
(Hz)	(dB)	m²	(dB)	(dB)	(dB)	LIMIT	DEFICIENCIES
50	39.8	29.8	108	74	31	4.3	-
63	34.1	27.0	108	65	40	3.6	-
80	38.4	19.7	113	73	39	3.4	-
100	34.6	14.4	109	70	38	2.6	-
125	29.2	12.6	107	66	41	1.6	0
160	26.5	9.9	105	65	41	1.0	0
200	23.6	10.7	104	58	46	1.8	0
250	17.6	10.3	101	55	48	1.1	0
315	20.3	9.3	106	57	50	0.7	0
400	15.0	8.5	102	56	48	0.7	5
500	17.6	8.0	102	57	46	0.5	8
630	19.8	7.8	103	55	49	0.5	6
800	19.7	7.7	102	53	51	0.4	5
1000	19.4	7.8	103	50	55	0.3	2
1250	15.5	7.8	103	45	60	0.3	0
1600	10.0	8.0	102	41	63	0.4	0
2000	8.5	9.3	103	41	64	0.4	0
2500	6.0	10.2	101	37	66	0.4	0
3150	4.4	11.6	101	37	65	0.4	0
4000	4.8	13.3	100	37	63	0.4	0
5000	5.3	15.8	100	34	64	0.5	-
6300	6.0	20.4	99	31	66	0.7	-
8000	6.5	27.0	98	32	63	0.9	-
10000	6.7	27.0	98	31	64	1.2	-
STC Ratin	54	(Sound Transmi	ssion Class)		Sum o	f Deficiencies	26

Notes:

- 1) Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.
- 2) Specimen TL levels listed in  $\ensuremath{\textit{red}}$  are potentially limited by the laboratory flanking limit.
- 3) Specimen TL levels listed in <u>blue</u> indicate the lower limit of the transmission loss.
- 4) Specimen TL levels listed in  $\ green \ \ indicate that there has been a filler wall correction applied$



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# TEST REPORT FOR CLARKDIETRICH BUILDING SYSTEMS, LLC


Report No.: J4775.01-113-11-R1

Date: 05/20/19

## **SECTION 11**

# **TEST RESULTS - AIRBORNE SOUND TRANSMISSION LOSS GRAPH**

TEST DATE DATA FILE NO. CLIENT DESCRIPTION	25.4 mm (1") USG Levelr N25™ Sound Attenuatior Unfaced R-13 Fiberglass Sound Clip Resilient Sour	ilding Systems, LLC ock® Brand CSD® Early Exposure n Mat, 14.57 mm (0.57") 22-Gaug Insulation, 254 mm (10") ClarkDi nd Isolation Clip, 22.3 mm (0.88") FIRECODE® C Core Gypsum Pane	ge Corrugated Stee etrich TradeReady ClarkDietrich® 08	el Floor Deck, 88.9 mm (3.5") Steel Joist, 31.75 mm (1.25)	Johns Manville ') ClarkDietrich®
SPECIMEN AREA	10.98 m <sup>2</sup>	Receive Temp.	17.5°C (63.5°F)	Source Temp.	18.2°C (64.7°F)
TECHNICIAN	DRD	Receive Humidity	52%	<b>Source Humidity</b>	52%





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# TEST REPORT FOR CLARKDIETRICH BUILDING SYSTEMS, LLC

Report No.: J4775.01-113-11-R1

Date: 05/20/19

## **SECTION 12**

# **TEST RESULTS - IMPACT SOUND TRANSMISSION**

DATA FILE NO. CLIENT DESCRIPTION	25.4 mm (1") USG Levelr N25™ Sound Attenuatior Unfaced R-13 Fiberglass Sound Clip Resilient Sour	Iilding Systems, LLC  Tock® Brand CSD® Early Exposure In Mat, 14.57 mm (0.57") 22-Gaug Insulation, 254 mm (10") Clarkbi Ind Isolation Clip, 22.3 mm (0.88") FIRECODE® C Core Gypsum Pane	e Corrugated Stee etrich TradeReady ClarkDietrich® 08	el Floor Deck, 88.9 mm (3.5") ® Steel Joist, 31.75 mm (1.25'	Johns Manville ') ClarkDietrich®
SPECIMEN AREA	10.98 m²	Maximum Temp.	17.6°C (63.7°F)	Minimum Temp.	17.4°C (63.3°F)
TECHNICIAN	DRD	Max. Humidity	53%	Min. Humidity	51%

FREQ	BACKGROUND SPL	ABSORPTION	NORMALIZED IMPACT SPL	95% CONFIDENCE	NUMBER OF
(Hz)	(dB)	m²	(dB)	LIMIT	DEFICIENCIES
50	39.3	32.3	69	2.2	-
63	35.1	23.7	64	2.8	-
80	35.8	18.1	67	1.3	-
100	35.5	15.1	65	1.6	0
125	34.9	11.8	65	1.5	0
160	27.5	10.1	64	0.7	0
200	22.4	11.2	64	0.7	0
250	18.4	10.0	64	0.8	0
315	21.2	9.6	65	0.4	0
400	15.7	8.4	67	0.3	0
500	19.6	8.1	68	0.3	1
630	20.8	7.9	67	0.3	1
800	21.2	7.7	69	0.2	4
1000	20.1	7.8	67	0.2	3
1250	15.2	7.9	65	0.2	4
1600	10.6	8.1	63	0.3	5
2000	9.2	9.3	60	0.3	5
2500	6.6	10.1	55	0.2	3
3150	4.6	11.5	52	0.3	3
4000	5.0	13.5	46	0.3	-
5000	5.5	15.8	38	0.5	-
6300	6.1	20.1	30	0.8	-
8000	6.6	27.2	25	1.0	-
10000	6.7	27.2	14	0.9	-
IIC Rating	43	(Impact Insulati	on Class)	Sum of Deficiencies	29

**Notes:** Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# TEST REPORT FOR CLARKDIETRICH BUILDING SYSTEMS, LLC


Report No.: J4775.01-113-11-R1

Date: 05/20/19

## **SECTION 13**

# **TEST RESULTS - IMPACT SOUND TRANSMISSION GRAPH**

TEST DATE	3/19/2019					
DATA FILE NO.	J4775.01	-//5.01				
CLIENT	ClarkDietrich Bu	rkDietrich Building Systems, LLC  ACCREDITEI Testing Laboratory				
DESCRIPTION	N25™ Sound Attenuation Unfaced R-13 Fiberglass Sound Clip Resilient Soun	5.4 mm (1") USG Levelrock® Brand CSD® Early Exposure™ Floor Underlayment, 6.4 mm (0.25") USG Levelrock® Brand SAM- 25™ Sound Attenuation Mat, 14.57 mm (0.57") 22-Gauge Corrugated Steel Floor Deck, 88.9 mm (3.5") Johns Manville nfaced R-13 Fiberglass Insulation, 254 mm (10") ClarkDietrich TradeReady® Steel Joist, 31.75 mm (1.25") ClarkDietrich® bund Clip Resilient Sound Isolation Clip, 22.3 mm (0.88") ClarkDietrich® 087F125-18 Furring/Hat Channel, 15.9 mm (0.63") SG SHEETROCK® Brand FIRECODE® C Core Gypsum Panel				
SPECIMEN AREA	10.98 m <sup>2</sup>	Maximum Temp.	17.6°C (63.7°F)	Minimum Temp.	17.4°C (63.3°F)	
TECHNICIAN	DRD	Max. Humidity	53%	Min. Humidity	51%	





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# TEST REPORT FOR CLARKDIETRICH BUILDING SYSTEMS, LLC

Report No.: J4775.01-113-11-R1

Date: 05/20/19

# **SECTION 14**

# **PHOTOGRAPHS**



Photo No. 1 Source Room View of Test Specimen Installation



Photo No. 2
Receive Room View of Test Specimen Installation



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

# TEST REPORT FOR CLARKDIETRICH BUILDING SYSTEMS, LLC

Report No.: J4775.01-113-11-R1

Date: 05/20/19

# **SECTION 15**

## **REVISION LOG**

<b>REVISION</b> #	DATE	PAGES	DESCRIPTION
R0	04/15/19	N/A	Original Report Issue
R1	05/20/19	All	Sound clip name corrected