

STING

WESTERN ELECTRO - ACOUSTIC LABORATORY

O CALIBRATION • RESEARCH

25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

SOUND TRANSMISSION LOSS TEST REPORT NO. TL20-415

CLIENT: ClarkDietrich 10 September 2020

9050 Centre Point Drive, #400 West Chester, Ohio 45069

TEST DATE: 13 August 2020

INTRODUCTION

The test was performed in accordance with ASTM E 90-09 (2016), Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and ASTM E2235-04 (2020), Standard Test Method for Determination of Decay Rates for Use in Sound Insulation Test Methods.

Copies of the test standard are available at www.astm.org. The test chamber source and receiving room volumes are 204 and 148.4 cubic meters respectively. Western Electro-Acoustic Laboratory is accredited by the United States Department of Commerce, National Institute of Standards and Technology under the National Voluntary Accreditation Program (NVLAP) Lab Code 100256-0 for this test procedure. This test report relates only to the item(s) tested. This report must not be used to claim product certification, approval, or endorsement by WEAL, NVLAP, NIST or any agency of the federal government.

DESCRIPTION OF TEST SPECIMEN

The test specimen consisted of a ClarkDietrich ProSTUD® and ProTRAK® 30mil single steel stud wall assembly with ClarkDietrich RC Deluxe® resilient channel, Type 'X' gypsum board installed on both sides of the assembly, and batt insulation in the stud cavity.

TEST CONFIGURATION

Source Room Layers	Resilient Framing	Stud Framing	Receiving Room Layers	
2 layers 16 mm (5/8 inch) Type 'X' gypsum board	13 mm (1/2 inch) ClarkDietrich RC Deluxe® resilient channel with standard pre-drilled holes punched in the mounting flange of the channel	92 mm (3-5/8 inch) ClarkDietrich ProSTUD® and ProTRAK® 30mil single steel studs spaced 610 mm (24 inches) on center with R-13 batt insulation in the cavity	1 layer 16 mm (5/8 inch) Type 'X' gypsum board	

- The framing consisted of 92 mm (3-5/8 inch) ClarkDietrich ProSTUD® 30mil single steel studs that were spaced 610 mm (24 inches) on center (O.C.) and were screwed to the ClarkDietrich ProTRAK® 30mil steel track with 12 mm (1/2 inch) truss screws. Unfaced R-13 fiberglass insulation was installed in the stud cavities. The frame was isolated from the test opening with 6 mm (1/4 inch) neoprene pads.
- On the source side, ClarkDietrich RC Deluxe® standard resilient channel was installed per the manufacturer's instructions.
 - The channel was screwed to the studs using 11 mm (7/16 inch) pan framing head screws.
 - The channel was spaced 51 mm (2 inches) from the bottom track, 152 mm (6 inches) from the top track, and 610 mm (24 inches) O.C. vertically up the studs.
 - The channel had standard pre-drilled holes punched in the mounting flange of the channel.
- On the source side, two layers of 16 mm (5/8 inch) Type 'X' gypsum board were screwed to the channel.
 - The base layer was screwed using 25 mm (1 inch) long #6 drywall screws spaced at 305 mm (12 inches) O.C. along the channel.





STING

WESTERN ELECTRO - ACOUSTIC LABORATORY

CALIBRATION • RESEARCH

25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

SOUND TRANSMISSION LOSS TEST REPORT NO. TL20-415

CLIENT: ClarkDietrich 10 September 2020

9050 Centre Point Drive, #400 West Chester, Ohio 45069

TEST DATE: 13 August 2020

- The outer layer was screwed using 41 mm (1-5/8 inch) long #6 drywall screws offset from the first layer and spaced at 305 mm (12 inches) O.C. along the channel.
- On the receiving side, one layer of 16 mm (5/8 inch) Type 'X' gypsum board was screwed to the stud using 29 mm (1-1/8 inch) long #6 drywall screws spaced at 203 mm (8 inches) O.C. around the perimeter and 305 mm (12 inches) O.C. in the field.
- All gypsum board was oriented vertically with joints staggered on opposite sides. All gypsum board
 joints were sealed with a bead of latex caulking and metal foil tape. All screw heads were covered
 with metal foil tape.
- The overall dimensions of the wall assembly were 2.44 m (96 inches) wide by 2.44 m (96 inches) high by 152 mm (6 inches) thick.
- The overall weight of the assembly was estimated to be 219.2 kg (483.3 lbs.) for a calculated surface density of 36.9 kg/m² (7.6 lbs./ft²).

RESULTS OF THE MEASUREMENTS

One-third octave band sound transmission loss values are plotted and tabulated on the attached sheet. ASTM minimum volume requirements are met at 80 Hz and above. The Outdoor-Indoor Transmission Class rating determined in accordance with ASTM E 1332-10a was OITC 40. The Sound Transmission Class rating determined in accordance with ASTM E 413-10 was STC 55.

Approved:

Stephen A. Martin, Ph.D., P.E

Laboratory Director

Respectfully submitted, Western Electro-Acoustic Laboratory

Raul Martinez

Acoustical Test Technician





STING

WESTERN ELECTRO - ACOUSTIC LABORATORY

CALIBRATION

RESEARCH


25132 Rye Canyon Loop Santa Clarita, California 91355 Tel: (661) 775-3741 Fax: (661) 775-3742 www.weal.com

SOUND TRANSMISSION LOSS TEST REPORT NO. TL20-415

CLIENT: ClarkDietrich 10 September 2020

9050 Centre Point Drive, #400 West Chester, Ohio 45069

TEST DATE: 13 August 2020



1/3 OCT BAND CNTR FREQ		63	80	100	125	160	200	250	315	400	500
TL in dB		15	22	30	34	41	47	50	53	55	56
95% Confidence in dB		1.42	1.92	2.07	1.47	0.89	0.76	0.80	0.52	0.36	0.38
deficiencies					(5)	(1)					
1/3 OCT BAND CNTR FREQ		630	800	1000	1250	1600	2000	2500	3150	4000	5000
TL in dB		58	59	59	60	59	53	51	55	58	59
95% Confidence in dB		0.29	0.44	0.38	0.39	0.36	0.56	0.55	0.31	0.32	0.50
deficiencies						(0)	(6)	(8)	(4)	(1)	
EWR OITC	Test Date: 13 August 2020										STC
57 40	Specimen Area: 64 sq.ft.									55	
Temperature: 80.2 deg. F									(25)		

Relative Humidity: 32 %

